



1995 CAT  
322L  
TRACK EXCAVATORS

INSPECTION DETAILS

|                   |                          |
|-------------------|--------------------------|
| Inspection Type   | Consignment              |
| Inspection Form   | Standard                 |
| Inspection #      | 10226107                 |
| Inspection Status | Inspected                |
| Created           | 08/26/25 10:46:30        |
| Updated           | 08/28/25 12:42:58        |
| Created By        | Fuentes, David A.        |
| Inspector         | Fuentes, David A.        |
| Salesperson       | Schultis, Derrick R.     |
| Serial #          | 9RL00726                 |
| SMU / Hours       | 10,424                   |
| Location          | Globe, AZ, United States |



FEATURES

General

- Air Conditioner
- Coupler - Quick
- Hand and Foot Control
- Stick
- Boom - 1 Piece
- Coupler Type - Hydraulic
- Lighting
- Car Body - Standard
- Engine Enclosures
- Mirrors

Attachments

- Bucket

CONDITION

Good

Fair

Poor

Approved Repair

GENERAL CONDITION

|  |   |  |
|--|---|--|
| Body<br><div><div></div><div></div><div></div></div> | Frame<br><div><div></div><div></div><div></div></div> | General<br><div><div></div><div></div></div><br>Machine is infected with pack rats it has a lot of rat feces |
| ET Product Status Report Download<br>NO              | Machine Starts and is Operable<br>YES                 | Visible Oil Leaks<br>YES   |

GENERAL APPEARANCE

|  |  |   |
|--|--|---|
| Bumper<br><div><div></div><div></div></div><br>Both sides of bumper have multiple dents and plastic bumper under front windshield is ripped. | 10<br>Car Body<br><div><div></div><div></div><div></div></div>                         | Counterweight<br><div><div></div><div></div><div></div></div>                           |
| Crankcase Guard / Battery Box<br><div><div></div><div></div></div><br>Multiple panels under the house are bent and or missing                | 4<br>Decals<br><div><div></div><div></div></div><br>All decals are faded and scratched | Eng. Enclose Hood / Stack<br><div><div></div><div></div><div></div></div>               |
| Engine Doors<br><div><div></div><div></div></div><br>Both rear door for radiator and pumps are bent  | 3<br>Fuel Tank<br><div><div></div><div></div></div><br>Fuel cap breather is broken     | 1<br>Grab Irons<br><div><div></div><div></div></div><br>Left front grab iron is bent    |
| Hood<br><div><div></div><div></div><div></div></div>   | Main Frame Welds<br><div><div></div><div></div><div></div></div>                       | Paint<br><div><div></div><div></div></div><br>Paint is faded and scratched              |
| Pre-Cleaner Bowl<br><div><div></div><div></div><div></div></div>   | Radiator Grill & Shroud<br><div><div></div><div></div><div></div></div>                | Sheet Metal<br><div><div></div><div></div></div><br>Tool box lid is bent will not close |

Steps / Ladder

Step on toolbox is cracked pushed down

Cleaning Required

YES

Machine has a lot of rat feces throughout machine

SAFETY ITEMS

Horn

Horn not working

Seat Belt / Date

Seat belt is outdated

Travel Alarm

ROPS

YES

Both front posts on ROPS have been hit and bent

9

ROPS Certification Plate

NO

Safety Decals In Place

NO

Safety Decals Legible

NO

OPERATOR STATION

Air Conditioner

Vent temperature 50° Ambient temperature 79°

Armrests

Dash Console

Rear console behind seat is missing the top cover

Door Latches / Hinges / Seals

Floor Boards / Mats

Gauges

Headliner

Head liner is dirty ( Functional )

Heater / Defroster

Hour Meter - GAUGES, OPERATION STATION, CONSOLE

10424

Hydraulic Controls

Interior Lights

Interior light not working

Mirrors

Monitoring Display  
●●●

Seat Cushions / Suspension / Type  
●●  
Both seat cushions are very dirty and stained ( Functional )

3 Switches  
●●●

Travel Controls (Type)  
●●  
Travel peddles are missing rubber covers

Windows  
●●●

Windshield Wipers  
●● 1  
Both wiper blades need replaced

Current O&MM  
**NO**  
No OMM

Current Safety Manual  
**NO**  
No safety manual

## ENGINE

Belts / Pulleys - ENGINE  
●●●

Engine Oil Level / Condition  
●●●

Engine Supports / Mounts  
●●●

Exhaust / Muffler / Stack  
●●●

Fuel Injection System  
●●●

Governor  
●●●

Intake / Air Filters  
●●●

Operating Condition - ENGINE  
●●●

Turbocharger / Blower  
●●●

Apparent Other Engine Damage  
**NO**

Blow By  
**YES**  
Machine has blowby

Fuel Leaks  
**NO**

Has Engine been rebuilt?  
**NO**

Knocking  
**NO**

Oil Leaks  
**NO**

Pre Lube System  
**NO**

Service Needed  
**YES**

Water in Oil  
**NO**

Engine S/N  
98Z09134

Hours On Engine  
10424

Oil Pressure (H/L/N)  
Normal

Smoke Color (B/D/L/W)  
Normal

COOLING SYSTEM

|  |  |   |
|--|--|---|
| Anti-Freeze Level / Color / Condition<br><div><div></div><div></div><div></div></div><br>Red | Belts / Pulleys - COOLING SYSTEM<br><div><div></div><div></div><div></div></div> | Coolers<br><div><div></div><div></div><div></div></div>       |
| Fan<br><div><div></div><div></div><div></div></div>  | Fan Shrouds / Guards<br><div><div></div><div></div><div></div></div>             | Hoses / Tubes<br><div><div></div><div></div><div></div></div> |
| Radiator<br><div><div></div><div></div><div></div></div>                                     | Water Pump<br><div><div></div><div></div><div></div></div>                       |   |
| Compression in Radiator<br>NO  | Coolant Leaks<br>NO  | Oil in Anti-Freeze<br>NO                                      |
| Standard Radiator<br>YES   |  |   |

ELECTRICAL, STARTING AND CHARGING SYSTEM


|  |  |  |
|--|--|--|
| Alternator<br><div><div></div><div></div><div></div></div> | Batteries / Cables / Master Disconnect<br><div><div></div><div></div><div></div></div> | Lighting<br><div><div></div><div></div><div></div></div> |
| Starter<br><div><div></div><div></div><div></div></div>    | Wiring<br><div><div></div><div></div><div></div></div>                                 |  |

HYDRAULICS


|  |   |  |
|--|---|--|
| Boom Cylinder<br><div><div></div><div></div><div></div></div>  | Bucket Cylinder<br><div><div></div><div></div></div><br>Bucket cylinder is leaking                      | Control Linkage<br><div><div></div><div></div><div></div></div>                  |
| Hose Lines<br><div><div></div><div></div></div><br>Suction hose at tank and filter and hose on bottom of valve are leaking | <div><div></div><div></div></div> 3<br>Hydraulic Swivel<br><div><div></div><div></div><div></div></div> | Operating Condition - HYDRAULICS<br><div><div></div><div></div><div></div></div> |
| Pump Drive<br><div><div></div><div></div><div></div></div>   | Pumps & Valves<br><div><div></div><div></div><div></div></div>  | Rotex<br><div><div></div><div></div><div></div></div>                            |

Stick Cylinder  



Swing Gear  


Swing Motors  



Tank  


Travel Motors  


BOOM


Boom Condition  
  
Boom has multiple repairs done. All repairs have cracks starting at repairs.


4 Boom Pins  



Pins & Bushings - BOOM  
  
Pins and bushing have some movement ( FUNCTIONAL )

Boom Length (Actual Length)  
19' 4"

STICK


Pins & Bushings - STICK  



Stick Conditions  



Stick Pins  
  
Stick to coupler is worn with movement

Stick Length  
9' 8"


BUCKET

Bucket Bottom  


Bucket Linkage  
  
Bucket linkage is worn with movement

Bucket Mounts  


Bucket Sides  


Teeth / Adapters  


Quick Coupler  
**YES**  
JRB Coupler

Brand  
Cat

Width  
18"

UNDERCARRIAGE

|                            | Measurement (L) | % Worn (L) | Total Potential Hours (L) | Measurement (R) | % Worn (R) | Total Potential Hours (R) |
|----------------------------|-----------------|------------|---------------------------|-----------------|------------|---------------------------|
| Carrier Rollers Front      | 4.72            |            |                           | 4.72            |            |                           |
| Carrier Rollers Rear       | 4.72            |            |                           | 4.72            |            |                           |
| Idlers Front               | ..88            | 48         |                           | .88             | 48         |                           |
| Links                      | 4.12            | 27         |                           | 4.12            | 27         |                           |
| Pins & Bushings (External) | 2.40            | 48         |                           | 2.40            | 48         |                           |
| Track Roller 1             | .70             | 48         |                           | .70             | 48         |                           |
| Track Shoe Grouser Height  | .60             | 56         |                           | .60             | 56         |                           |

|  |   |                                    |
|--|---|------------------------------------|
| Track Frame - Left<br><div><div></div><div></div><div></div></div> | Track Frame - Right<br><div><div></div><div></div><div></div></div> |                                    |
| Pins & Bushings Turned?<br><b>YES</b>                              |   |                                    |
| Cannon<br>Good   | Carrier Rollers<br>Good   | Idlers<br>Good                     |
| Links<br>Good  | Pins & Bushings (External)<br>Good                                  | Pins & Bushings (Internal)<br>Good |
| Segments<br>Good   |   |                                    |

FINAL DRIVES

|  |   |  |
|--|---|--|
| Housings, Left<br><div><div></div><div></div><div></div></div> | Housings, Right<br><div><div></div><div></div><div></div></div> | Planetaries / Differential, Left<br><div><div></div><div></div><div></div></div> |
|--|---|--|





MARKETING PHOTOS (17)

